

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Midway Drilling, Inc.

Complete Address P. O. Box 921, Great Bend, Kansas 67530

Lease Name Koriel "A" Well No. 5

Location SW NW SE NW Sec. 23 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3556'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 10:15 A Day 26 Month 4 Year 1974

The above well was plugged as follows:

Total Depth 3556' 15 1/2' csg 144' W/110 sk. 10 3/4' csg 995' W/385' sx cem.

7" csg 3551' W/100' sx cem.

Filled 7" csg W/sd 3556-3525) dumped 6 sk cem W/dump bailer. (3490-3525)

Cutoff and recovered 1426' of 7" csg.

Filled 10 3/4' csg with mud to 350' -set rock & sand bridge (350-325)

Filled with readymix cement from 325' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Res. J. Massey
Well Plugging Supervisor

INVOICED

DATE 5/1/74

INV. NO. 9011-W