

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Midway Drilling, Inc.

Complete Address P. O. Box 921, Great Bend, Kansas 67530

Lease Name Koriel "A" Well No. 3

Location CSL NW Sec. 23 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3555'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 7 P Day 22 Month 4 Year 1974

The above well was plugged as follows:

Total Depth 3555' 12 1/2" csg set at 221' 10 3/4" csg depth & cement unknown.

7" csg set at 3501' cem. (?)

PBTD 3005' -poured 55 gal sand -dumped 6 sk cem W/dump bailer. (2950-3005)

Cutoff and recovered 1746' of 7" csg.

Filled 10 3/4" csg with mud to 359' -set rock & sand bridge (350-325)

Dumped readymix cement from 325' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey
Well Plugging Supervisor

INVOICED

DATE 4/26/74
INV. NO. 9000-W