

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 12-15 County: Rush

Location: SE SE NW Sec. 20 Twp. 18 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 5605

I have this date completed supervision of plugging of:

Lease Name: Huenergardt Well No. 1

Operator's Full Name: Skelly Oil Co

Complete Address: Box 391 Hutchinson, Kans

Plugging Contractor: West Supply Co & Halliburton Co

Address: West Supply Co Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 31 Month 1 Year 59

The above well was plugged as follows:

8 5/8" at 1011' circulated with cement - 5 1/2" 3557' with 120 sax.

4" liner 3309' to 3305', perforated 3341'

Filled with sand to 3325', set 4 sax cement with dump bailer, pulled

1900' 5 1/2" - pumped hole full heavy mud (50 sax Gel) pumped cementing

plug to 400', followed by 150 sax cement - cement 400' to 0'.

Mudding and cementing by Halliburton Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION

Signed: *Jewel M. Ogden*
Conservation Division Agent

Reviewed: *J. Louisa Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 20 T. 18 R. 16W
BOOK PAGE 12 LINE 13