

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 - 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Mellies Well No. # 1

Location NW SW SE Sec. 31 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 4:45 PM Day 29th Month April Year 1966

The Above well was plugged as follows:

261' of 8 5/8" surface pipe, cemented with 275 sacks. 3599' of 4 1/2" long
string, cemented with 125 sacks. Top perforation 3529'. Bottom of the hole
was sanded to 3500', and cemented with 3 sacks, through the dump bailer.
2793' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed
in fluid to 255', rock bridge from 255' to 245'. 8 sacks of cement was mixed
in barrel, and put on plug at 245', through the dump bailer, and let set over-
night. 3 days later hole was bailed dry, and 17 sacks of cement was added to
the plug. Hole was filled with drilling mud to 40', rock bridge from 40' to
30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/3/66
INV. NO. 3151-W