

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-159-21,312

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name GulFco Production, Inc.

Complete Address 1900 W. Loop South, Suite 1900, Houston, Texas

Lease Name Hauschild Well No. 1-15

Location 40'E + 10'S OF C SW 1/4  
700' EWB 650' N15E Sec. 15 Twp. 21 Rge. 7 (~~East~~)(West)

County Rice Total Depth 3470'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Damac Drilling, Inc. and Dowell

Address Box 1164, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: Noon Day: 8 Month: November Year: 1981

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows: 8 3/8" - 200' - 175 sacks

Hole circulated and Filled with mud. 50 sacks, 50-50 Perm mix w/2% gel and 3% C.C. pumped through drill pipe at 300'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of collar with 10 sacks cement. Rathole cemented with 10 sacks cement. Mousehole cemented with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 17 1981  
11-17-81  
CONSERVATION DIVISION  
Wichita Kansas

I hereby certify that the above plugging instructions were given as herein stated. **NOTICED**

Signed: [Signature]  
Conservation Division Agent

DATE 12-1-81  
INV. NO. 8653-W