

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-185-230660000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate s or completion date

WELL OPERATOR: Globe Operating, Inc. KCC LICENSE # 6170
(owner/company name) (operator's)

ADDRESS: P.O. Box 12 CITY: Great Bend

STATE: Kansas ZIP CODE 67530 CONTACT PHONE: 316-792-7607

LEASE: Fischer 'A' WELL#: No. 1 Section 31 Township 21s Range 11w

80' W & 210' S of C Ne Sw Nw SPOT LOCATION/QQQQ COUNTY: Stafford

1860 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)

910 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well Gas Well D&A XX SWD/ENHR WELL Docket #
CONDUCTOR CASING SIZE None SET AT CEMENTED WITH SACKS
SURFACE CASING SIZE 8-5/8" SET AT 271 KB CEMENTED WITH 230 SACKS
PRODUCTION CASING SIZE None SET AT CEMENTED WITH SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1778 G.L. 1787 K.B. T.D. 3570 PBTD Anhydrite Depth
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING:
Plugged well with : Heavy mud from 3570' to 570' then 50 sacks of cement,
then heavy mud to 300' then 50 sacks cement then heavy mud to 40' then 10 sacks.
Plugged rathole with 15 sacks and mousehole with 10 sacks using 60/40 Poz, 6% Gel.
Received plugging orders at 9:00 am on 11/10/97 from Steve Durrant. Started
plugging well at 8:30 pm and plug down at 10:30 pm on 11/12/97 by Allied. Ticket #9665.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Vaughn Thompson/Steve E. McClain Phone#: (316) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR : Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 10:30 pm on November 12, 1997.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: _____

DATE: 11/12/97 AUTHORIZED OPERATOR OR AGENT: _____

Operator: Steve E. McClain Agent _____
STATE CORPORATION COMMISSION
(signature) Steve E. McClain, Agent for Operator
JAN 15 1998

CONSERVATION DIVISION
Wichita, Kansas

1-15-1998