


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 15 Twp. 21 Rge. 23 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SE SW

Lease Owner Sulpetro International, Ltd.
Lease Name Marie Wellensick Well No. 1
Office Address 4925 Greenville Ave., Dallas, Texas 75206
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 1/27/79 19
Application for plugging filed 1/27/79 19
Application for plugging approved 1/27/79 19
Plugging commenced 1/27/79 19
Plugging completed 1/27/79 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations. TD 4625'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	568	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Bottom plug at 600' with 50 sacks 50/50 Poz 6% gel

Top & bridge at 40' with 10 sacks 50/50 Poz 6% gel

5 sacks in rathole

Job complete 1:30 p.m. 1/27/79

RECEIVED
STATE CORPORATION COMMISSION
FEB - 6 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bill Rowe, Box 1131, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
James C. Remsberg (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.


(Signature)

James C. Remsberg
200 Douglas Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of February, 1979

Mary Lou Taylor
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

OPERATOR: Sulpetro International, Ltd.
1100 One Energy Square Building
4925 Greenville Avenue
Dallas, Texas 75206

LEASE: Marie Wellensick No. 1
C SE SW Sec. 15-21S-23W
Hodgeman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 1/17/79

COMPLETED: 1/27/79

RTD: 4625'

CASING: 8-5/8" set at 568' with 350 sx cement

0' to 900' Clay & Shale (575' 12 1/4" Surface hole)
900' to 1063' Shale Blaine @ 970'
1063' to 1265' Sand
1265' to 1625' Shale
1625' to 2000' Shale & Shells
2000' to 2358' Shale
2358' to 2550' Shale & Shells
2550' to 3190' Shale & Lime
3190' to 4508' Lime & Shale (Lime at 4508)
4508' to 4571' Lime & Shale
4571' Mississippian & Lime
4571' to 4625' Mississippian
4625' RTD

RECEIVED
STATE CORPORATION COMMISSION

FEB - 6 1979

STATE OF KANSAS

COUNTY OF SEDGWICK

CONSERVATION DIVISION
Wichita, Kansas

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the log on the Marie Wellensick No. 1 for Sulpetro International, Ltd.


James C. Remsberg

Subscribed and sworn this 5th day of February, 1979


Mary Lou Taylor, Notary

My commission expires January 17, 1981

