


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 21 Twp. 21 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Beardmore Drilling Company
Lease Name Bauer "A" Well No. 1
Office Address 700 - One Twenty Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 20 1966
Application for plugging filed November 20 1966
Application for plugging approved November 20 1966
Plugging commenced November 20 1966
Plugging completed November 20 1966
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well E. Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4370 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface soil		0	40			
Sand and shale		40	172			
Sand		172	212			
Shale and shells		212	389	8-5/8"	389'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

0 to 30' - 10 sacks cement - 1st plug
30' to 390' - 30 sacks cement - 2nd plug
390' to 700' - 40 sacks cement - 3rd plug
700' to 4370' - heavy mud

RECORDED
STATE CORPORATION COMMISSION
DEC 1 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Cementing Company
Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Leonard P. Tolle (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard P. Tolle
700 - One Twenty Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of November, 19 66

My commission expires 7-13-67
Shirley Ann Jackson
Shirley Ann Jackson Notary Public.



GABBERT-JONES, INC.
WICHITA, KANSAS.
DRILLERS' WELL LOG

BAUER "A" #1
 C NE SW SECTION 21-21S-21W
 HODGEMAN COUNTY, KANSAS

COMMENCED: NOVEMBER 8, 1966
 COMPLETED: NOVEMBER 20, 1966

OPERATOR - BEARDMORE DRILLING Co.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	40	SURFACE SOIL AND CLAY	
40	85	SAND	
85	172	SHALE	
172	212	SAND	
212	250	SHALE	
250	389	SHALE AND SHELLS	RAN 19 JOINTS OF 8-5/8" CASING, SET @ 389' w/250 SACKS CEMENT.
389	416	SHALE AND SHELLS	
416	615	RED BED	
615	628	ANHYDRITE	
628	710	SHALE	
710	910	SAND	
910	1269	SHALE	
1269	1302	ANHYDRITE	
1302	2260	SHALE AND SHELLS	
2260	2789	SHALE AND LIME	
2789	2840	SHALE	
2840	3770	SHALE AND LIME	
3770	4370	LIME	
4370	TD		DRY AND ABANDONED.

RECEIVED
 STATE OF KANSAS COMMISSIONER
 DEC 7 1966
 CONSERVATION DIVISION
 TOPEKA, KANSAS

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NE SW SECTION 21-21S-21W, HODGEMAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 25TH DAY OF NOVEMBER, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.