

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

McPherson County, Sec. 16 Twp. 21 Rge. 2W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Brunson Production & Exploration, Inc.

Lease Name Stucky F Well No. One

Office Address 333 First National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-3-57 19

Application for plugging filed " " " 19

Application for plugging approved " " " 19

Plugging commenced " " " 19

Plugging completed " " " 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkey

Producing formation Depth to top Bottom Total Depth of Well 3478 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	167'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole circulated with very heavy mud. D.P. laid down. Pushed plug to 157'. Covered with 4 sacks of fiber seal and bridged to hold weight of 6 jts. of D.P. 16 sacks cement mixed and poured through 5 jts. of D.P. Hole filled to 35' of cellar bottom. Plug pushed to 35' covered with 3 sks. of fiber seal & 5 sks. of cement, filling hole to cellar bottom. All plugs secured with two strands of HOWCO steel line.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 8 X 1957

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Brunson Production & Exploration, Inc.

Address 333 First National Bank Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

I, Ralph B. McLaughlin (employee of owner) or (owner/producer) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B. McLaughlin  
333 1st National Bank Bldg., Wichita (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of June, 19 57

Wanda Lou Bruce  
Wanda Lou Bruce Notary Public.

My commission expires March 6, 1961

PLUGGING  
FILE SEC 16 T 21 R 2W  
BOOK PAGE 19 LINE 18

BRUNSON PRODUCTION & EXPLORATION, INC.  
WICHITA, KANSAS

WELL: STUCKY "F" # 1

SE SE SE

COMMENCED RD: 5-23-57

16-21-2W

COMPLETED RD: 6-3-57

MCPHERSON COUNTY

TOTAL DEPTH: 3478'

ELEVATION: 1491 DF

CASING: 167' 8 5/8" O.D. 28 1/2#

CONTRACTOR: BRUNSON  
PRODUCTION & EXPLORATION, INC.

STRATA	DEPTH	TOPS	
Surface Soil & Clay	25	Lansing	2353 --860
Sand & Clay	60	Shaly Conglomerate	2975 -1482
Shale & Red Beds	100	Mississippian	3008 -1515
Shale & Shells	155	Mississippi Lime	3072 -1579
Shale	330	Kinderhook	3279 -1786
Shale & Lime	410	Misener Sand	3378 -1885
Broken Lime	535	Hunton	3380 -1887
Shale & Shells	600	Maquoketa	3384 -1891
Lime & Shale	650	Viola	3467 -1974
Sand	665		
Shale	695		
Shale & Lime	1750		
Lime	1970		
Lime & Shale	3016		
Lime & Chert	3205		
Lime	3235		
Lime & Shale	3478		
Total Depth	3478		

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRUNSON PRODUCTION & EXPLORATION, INC.  
BY

*Ralph B. McLaughlin*  
Ralph B. McLaughlin-Secretary-Treas.

Signed and sworn to in my presence this 6th day of June, 1957, by Ralph B. McLaughlin, Secretary-Treasurer of Brunson Production & Exploration, Inc., a Corporation in the State of Kansas.

*Wanda Lou Bruce*  
Wanda Lou Bruce-Notary Public

My commission expires March 6, 1961.

PLUGGING  
FILE: SEC 16 T 21 R 2W  
BOOK PAGE 19 LINE 13