

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Harvey

County. Sec. 17 Twp. 22-S Rge. 3 (X) (W)

Location as "NE/CNW/SW" or footage from lines. C E/2 E/2
Lease Owner ~~Flaming~~ Oilfield Supply & Trading, Inc.

Lease Name Flaming Well No. 1

Office Address 430 Greenwood, Wichita, Kansas 67211

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5 - 8 19 71

Application for plugging filed 4 - 24 19 72

Application for plugging approved 4 - 25 19 72


Plugging commenced 5 - 24 19 72

Plugging completed 5 - 26 19 72

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott - Box -- 924 - Mcpherson, Kans.

Producing formation Simpson Sand Depth to top 3620 Bottom 3631 Total Depth of Well 3631 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Simpson Sand	Water	3620	3631	5 1/2	3621	2525

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 570 feet - rock bridge to 560 feet - dump 25 sax cement mud to 40 feet - rock bridge to 30 feet - dump 10 sax cement to surface, tear down.

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ralph Comstock Pepe Pulling, Inc.
Address 320 North Park, Stafford, Kansas 67578

STATE OF Kansas, COUNTY OF Sedgwick, ss.

W. R. Justice (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) W. R. Justice
W. R. Justice

(Address) _____

SUBSCRIBED AND SWORN to before me this 14 day of June, 1972
My commission expires 2, 1973
Maritak Jenkins
Notary Public.



TRIANGLE DRILLING

15.079-20166-0000

99

324 North Orchard

EL DORADO, KANSAS

To Oilfield Supply & Trading Inc.

Invoice No. _____

430 Greenwood

Date May 8, 1971

Wichita, Kansas

For Month Of _____

Lease Flaming # 1 C E1/2 E 1/2 NW, 17-21-34 Harvey County, Kansas

WELL LOG

0	15 Sand
15	45 Shale
45	311 Sand
311	630 Shale
630	910 Lime
910	1310 Lime and Shale
1310	1513 Shale
1513	1620 Lime
1620	2482 Lime and Shale
2482	2848 Lime K.C.
2848	3147 Lime and Shale
3147	3462 Lime Miss.
3462	3620 Lime Hunton
3620	3631 Sand Simpson R.T.D

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1972
CONSERVATION DIVISION
Wichita, Kansas

~~17-21-3W~~

6P

15.079.20166.0000

TRIANGLE DRILLING

324 North Orchard
EL DORADO, KANSAS

To Oilfield Supply & Trading Inc.
430 Greenwood
Wichita, Kansas

Invoice No: _____
Date May 6, 1971
For Month Of _____

Lease ~~Planing # 1-6 E 1/2 E 1/2 NW~~, ~~17-21-3W~~ Harvey County, Kansas

WELL LOG

0	-----	15 Sand
15	-----	45 Shale
45	-----	311 Sand
311	-----	630 Shale
630	-----	910 Lime
910	-----	1310 Lime and Shale
1310	-----	1513 Shale
1513	-----	1620 Lime
1620	-----	2482 Lime and Shale
2482	-----	2848 Lime K.C.
2848	-----	3147 Lime and Shale
3147	-----	3462 Lime Miss.
3462	-----	3620 Lime Hunton
3620	-----	3631 Sand Simpson R.T.D

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1972
CONSERVATION DIVISION
Wichita, Kansas