

STATE OF KANSAS
STATE CORPORATION COMMISSION
308 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-083-20394-0000

API NUMBER Comp. 1975

LEASE NAME Witman

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 24 TWP. 21S RGE. 25W (E) or (W)

COUNTY Hodgeman

Date Well Completed

Plugging Commenced 4-12-99

Plugging Completed 4-13-99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P.O. Box 97 Ellinwood, Kansas 67526

PHONE# (316) 564-2577 OPERATORS LICENSE NO. 5131

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4478

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	325'	None
				5-1/2"	4461'	1650'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from feet to feet each stage.
Dumped 2 sacks cement at top of bridge plug @4330'. Shot pipe loose @1650'. Pulled 53 fts of 5-1/2" casing. Ran in 800' of 2-3/8" tubing, pumped 175 sks cement w/500# hulls, pulled tubing to 60' and topped off with 15 sks cement. Plugging Complete 60/40 pos, 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES:

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts herein stated, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED

STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 16th day of April, 1999

Irene Herzberg
Notary Public

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires:

