

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Kearny County, Sec. 15 Twp. 21S Rge. (E) 38 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner Galaxy Oil Co.

Lease Name Harshbarger Well No. 1

Office Address 918 Lamar, Wichita Falls, Texas 76301

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 17, 19 72

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced December 17, 19 72

Plugging completed December 17, 19 72

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar Eves of Sublette)



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 5035' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	402'	8-5/8"	402'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 560 Feet,
100 sax Cement; Mud to 40', 35 sax Cement.
Job completed @ 3:00 A.M. by HOWCO.

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

Address Box 129, Liberal, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clarence Michael of Sage Drilling Co. (employee or owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael

500 Bitting Bldg., Wichita, Kansas (Address)

Subscribed and sworn to before me this 20th day of December 19 72

Louise K. Whitted
Louise K. Whitted - Notary Public.



DRILLERS LOG

HARSHBARGER NO. 1

CASING RECORD:	OPERATOR: Galaxy Oil Co.	DESCRIPTION:
8-5/8" @ 402' w/325 sax cement	CONTRACTOR: Sage Drilling Co.	SE SE NW Sec. 15-21S-38W Kearny County, Kansas
TOTAL DEPTH: 5035'	COMMENCED: November 30, 1972	COMPLETED: December 17, 1972

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Top Soil & Shale	0	170	
Shale	170	406	
Shale & Shells	406	970	
Shale	970	1430	
Sand & Shale	1430	1930	
Shale & Lime	1930	2174	
Anhydrite	2174	2202	
Shale & Lime	2202	2280	
Lime	2280	2543	
Lime & Shale	2543	2640	
Lime	2640	2685	
Lime & Shale	2685	2840	
Lime	2840	3053	
Lime & Shale	3053	3190	
Lime	3190	3475	
Lime & Shale	3475	3643	
Lime	3643	3935	
Lime & Shale	3935	4048	
Lime	4048	4285	
Lime & Shale	4285	4382	
Lime	4382	4650	
Lime & Shale	4650	4743	
Lime	4743	5035	D&A

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1972
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael

Subscribed and sworn to before me this 20th day of December, 1972.



Louise K. Whitted
Louise K. Whitted - Notary Public

My commission expires:
November 26, 1974.