


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Hodgeman County, Sec. 12 Twp. 21S Rge. 25 XX/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
1980' FSL & 660' FWL  
Lease Owner Kewanee Oil Company  
Lease Name Nuss Well No. 1  
Office Address P. O. Box 2093, Wichita, Kansas 67201  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed May 20 1977  
Application for plugging filed May 24 1977  
Application for plugging approved May 24 1977  
Plugging commenced May 21 1977  
Plugging completed May 21 1977  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
None 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes - Verbal

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom 4451' Total Depth of Well 4451'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	481	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug-set.

- Filled hole with mud to 900'. Cemented with 50 sacks cement.
- Filled hole with mud to 480'. Cemented with 35 sacks cement.
- Filled hole with mud to 40'. Set solid bridge and 15 sacks cement.
- Filled rat hole with 5 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

Copy of Drillers Log attached to original.

JUN 01 1977

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones Drilling Company

STATE OF Kansas COUNTY OF Sedgwick, ss.  
A. A. Lollar (employee of owner) ~~owner or operator~~


of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature)

*AA Lollar*

P. O. Box 2093, Wichita, Kansas 67201  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 1977.



*Billie Oden*

Billie Oden

Notary Public.

My commission expires 8-10-79

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Nuss #1  
 NW-SW Sec. 12-21S-25W  
 Hodgeman County, Kansas

Commenced: 5-8-77  
 Completed: 5-21-77

OPERATOR: KEWANEE OIL COMPANY

From	Depth To	Formation	Remarks
0	35	Top Soil-Clay	Ran 12 jts of 20# 8-5/8" csg set @ 481' w/notched texas pattern shoe - cent @ 475-441 cemented w/160 sks Howcolite 3% CC + 130 sks common 3% CC PD @ 1:00 p.m. 5-9-77
35	330	Sand-Shale	
330	382	Shale-Sand	
382	490	Shale	
490	1022	Shale-Sand	
1022	1225	Dakota-Sand	
1225	1275	Shale	
1275	1541	Shale-Redbed	
1541	1594	Anhy	
1594	1800	Shale-Shells	
1800	2365	Shale-Lime	
2365	3900	Lime-Shale	
3900	4335	Lime	
4335	4413	Lime-Cherty Lime	
4413	4451	Lime	

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 01 1977

D & A CONSERVATION DIVISION  
 Wichita, Kansas

4451 - TD

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
 JAMES S. SUTTON II

Subscribed and sworn to before me this 25th day of May, 1977.

*Marjorie Hall*  
 MARJORIE HALL-NOTARY PUBLIC

My Commission expires November 29, 1979.

