

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 31 Twp. 21 Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW NE

Lease Owner Duke & Wood Drilling Company

Lease Name Mellies Well No. 1

Office Address Box 123, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed December 31, 19 52

Application for plugging filed Dec. 31 19 52

Application for plugging approved Dec. 31 19 52


Plugging commenced Dec. 31 19 52

Plugging completed Dec. 31 19 52

Reason for abandonment of well or producing formation went dry

If a producing well is abandoned, date of last production Oct. 16, 19 52

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3532 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3516'	2866'
				8 5/8"	222'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rock from 3532 to 3460' and dumped 5 sacks of cement.

Pumped 20 sacks of mud in hole and followed with 60 sacks of cement.

Well plugged according to instructions of M. A. Rives, State Plugger.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Carroll Bros. Casing Pulling Co.

Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Cecil M. Olson (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M. Olson

Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 16th day of January, 1953

My commission expires April 29, 1953.

24-2675-5

RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1953

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 31 T 21 R 112
BOOK PAGE 70 LINE 5

Notary Public.

WELL LOG
Mellies # 1
NW NW NE Sec. 31-21-11
Stafford County, Kansas

Started December 26, 1950
Completed January 9, 1951

Anhydrite 515'
Heebner 3031' (-1262)
Brown Lime 3161' (-1392)
K.C. Lime 3176' (-1407)
Conglomerate 3452' (-1683)

0-220	Sand, red rock and red bed
220-545	Red bed, shale and anhydrite
545-1380	Red bed, shale and salt
1380-1485	Shale, shells and lime
1485-1795	Shale and lime
1795-2075	Shale and lime
2075-2360	Shale and lime
2360-2670	Shale and lime
2670-2862	Shale and lime
2862-3002	Lime
3002-3160	Lime
3160-3265	Lime
3265-3365	Lime
3365-3452	Lime
3452-3532	Conglomerate

TOTAL ROTARY DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton SS.

I, Lynn O. Duke, of the DUKE & WOOD DRUG Company, INC. being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Lynn O. Duke
Vice-President

Subscribed and sworn to before me this 27 day of March 1951.

RECEIVED
STATE COMMISSION
JAN 27 1953
CONSERVATION DIVISION
Wichita, Kansas

Dean L. Cooley
Notary Public

My commission expires: April 29, 1953.

PLUGGING
FILE SEC 31 T 21 R 1124
BOOK PAGE 70 LINE 5