

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County, Sec. 31 Twp. 21 Rge. (E) 11 (W)

Location as "NE/CNWxSWx" or footage from lines NW SW SE

Lease Owner SANTA-FE PIPE & SUPPLY, INC.

Lease Name MELLIES Well No. 1

Office Address BOX 562, GREAT BEND, KANSAS 67530

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed APRIL 1 19 66

Application for plugging approved APRIL 4 19 66


Plugging commenced APRIL 15 19 66

Plugging completed APRIL 29 19 66

Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. ELVING

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	261'	NONE
				4 1/2"	3599'	2803.25

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- 3600' - 3500' - SAND
- 3500' - 3464' - 3 SACKS CEMENT
- 3464' - 260' - MUD
- 260' - 250' - ROCK BRIDGE
- 250' - 229' - 7 SACKS CEMENT
- 229' - 175' - 18 SACKS CEMENT
- 175' - 40' - MUD
- 40' - 30' - ROCK BRIDGE
- 30' - BASE - 10 SACKS CEMENT

RECEIVED  
STATE CORPORATION COMMISSION

JUN - 3 1966

(If additional description is necessary, use BACK of this sheet)

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.

Address BOX 562, GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

T. L. NUTT

(~~employee of owner~~) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_

BOX 562, GREAT BEND, KANSAS 67530

(Address)

SUBSCRIBED AND SWORN TO before me this 20TH day of MAY, 19 66

Mary M. Guesnier  
Notary Public.

My commission expires JULY 31, 1966

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY 15.185.01184-0000  
 508 East Murdock, Wichita, Kansas


COPY

Company- WESTERN PETROLEUM CO.  
 Farm- Mellies No. 1

SEC. 31 T. 21 R. 11W  
 NW SW SE

Total Depth. 3600'  
 Comm. 12-3-60 Comp. 12-15-60  
 Shot or Treated.  
 Contractor. Western Petr.  
 Issued. 5-6-61

County Stafford  
 KANSAS



CASING:  
 8 5/8" 261' cem w/275 sx.  
 4 1/2" 3599' cem w/125 sx.

Elevation. 1764' KB

Production. 50 BOPD

Figures Indicate Bottom of Formations.

sand	30
clay, red bed	100
red bed	527
Anhydrite	548
shale & shells	1400
lime & shale	2340
shale & lime	2735
lime & shale	3010
lime	3600 RTD
Total Depth	

TOPS: SCOUT	
Anhydrite	518
Topeka	2730
Heebner	3020
Toronto	3036
Douglas	3052
Iatan	3149
Lansing	3172
Base Kansas City	3414
Conglomerate	3436
Viola	3442
Simpson	3465
Arbuckle	3513

**RECEIVED**  
 STATE CORPORATION COMMISSION

JUN - 3 1966

CONSERVATION DIVISION  
 Wichita, Kansas