


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rush County. Sec. 31 Twp. 19S Rge. 20W RAW
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
150' E of SW NW
Lease Owner Parrish Oil Company
Lease Name Young Well No. 1
Office Address 120 No. Market, Suite 201, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
Date Well completed May 15, 1977
Application for plugging filed Verbal Application 1977
Application for plugging approved Verbal Approval 1977
Plugging commenced May 15, 1977
Plugging completed May 15, 1977
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 1977
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4410'
Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS, OR WATER RECORDS		CASING RECORD				
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>MAY 23 1977</u>				<u>8-5/8"</u>	<u>313'</u>	<u>None</u>
<u>CONSERVATION DIVISION Wichita, Kansas</u>	<u>5-23-77</u>					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,410 ft. (rotary total depth) to 500 ft. Set plug at 500 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 500 ft. to 240 ft. Set plug at 240 ft. and cemented with 25 sacks cement. Filled hole with heavy rotary mud from 240 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 2 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4-1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (~~employee of owner~~) or (~~owner or operator~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th. day of May, 19 77



Elsie Willison
Elsie Willison - Notary Public.

My commission expires June 30, 1978

KANSAS GEOLOGICAL SOCIETY API # - 15-165-20-636-00-00
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Parrish Oil Company

SEC. 31 T. 19S R. 20W
 LOC. 150' E of SW NW

FARM Young NO. 1

TOTAL DEPTH 4,410'

COUNTY Rush

COMM. May 5, 1977


COMP. May 15, 1977

KANSAS

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED May 20, 1977



CASING

20	10	
15	8-5/8"	313' cemented w/200 sxs cement ELEVATION 2267 K.B.
12	6	
13	5	

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	360'
Sand and Shale	1,245'
Shale	1,491'
Anhydrite	1,513'
Shale	1,735'
Shale and Lime	2,036'
Shale	2,269'
Shale and Lime	2,560'
Lime and Shale	3,780'
Lime	4,410'
Rotary Total Depth	4,410'

RECEIVED
 STATE CORPORATION COMMISSION

MAY 23 1977

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
 Dean Britting

State of Kansas }
 County of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 20th. day of May, 1977.

Elsie Willison
 Elsie Willison - Notary Public

Commission Expires:

June 30, 1978

