


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rush County. Sec. 31 Twp. 19 Rge. 20 (E) W (W)
Location as "NE/CNWSW" or footage from lines C NE NE
Lease Owner Pickrell Drlg. Co.; Wichita, Kans. 67202
Lease Name Hamzy 'A' Well No. #1
Office Address 705 Fourth National Bank Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 5 19 70
Application for plugging filed November 5 19 70
Application for plugging approved November 5 19 70
Plugging commenced November 5 19 70
Plugging completed November 30 19 70
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4426 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	265	None
				5 1/2	4404	2457

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

November 5, 1970 Plugged off bottom. Dumped sand to 4300'. Mixed and dumped 5 sx of cement to 4260'.

November 30, 1970 Plugged off top. Globe Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing: 5 sx hulls - 20 sx gel - released plug and mixed and pumped 130 sx + 6 % gel cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1970
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Russ Casing Pulling, Inc.
Address P. O. Box 1082 ; Great Bend, Kansas 67530.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale M. Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale M. Robinson
Date M. Robinson
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 10th day of December, 19 70

My commission expires January 19, 1973
Esther Lamone
Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 9/20/70

Rotary Drilling Completed 9/29/70

LOCATION: Hamzy "A" No. 1, C NE NE Section 31-19S-20W
Rush County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 13 Jts. 8-5/8" surface casing set @ 265' KB. Cemented with 150 sacks cement. Completed 6:00 P.M. Circulated.

Run 146 Jts. 5-1/2" Casing set @ 4404'. Cemented w/135 sacks 50-50 Pozmix 4% gel followed by 35 sacks common. Plug down @ 4:35 A.M.
September 29, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

140	Post Rock & Shale		C.F.S.
266	Shale & Shells		4345
690	Shale, Sand Streaks		4400
900	Red Bed & Shale		4408
1120	Sand		
1482	Red Beds, Shale		
1511	Anhydrite		
1599	Shale & Shells		S.L.M.
2100	Shale	Board	4107.40
2830	Lime	Strap	4105.00
3360	Lime & Shale		2.40 Difference
3790	Shale & Lime		
3905	Lime & Shale		
4345	Lime		Slope Tests
4408	Cherty Lime, RTD		2000
			2500
			3000
			3500
			4000

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1970
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, Dale M. Robinson, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By Dale M. Robinson
Date W. Robinson Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

Ok this 5th day of October, 19 70, before me the undersigned, a Notary Public, in and for County and State aforesaid, personally appeared Dale M. Robinson, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamone
Esther Lamone Notary Public

