

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-185-19161-0000  
API NUMBER 04-17-61

LEASE NAME Mellies A

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3630 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 31 TWP. 21 RGE. 11 (W) or (W)

LEASE OPERATOR American Warrior, Inc.

COUNTY Stafford

ADDRESS P.O. Box 399, Garden City, Kansas 67846

Date Well Completed 04-17-61

PHONE# (316) 275-2963 OPERATORS LICENSE NO. 4058

Plugging Commenced 08-21-97

Character of Well Oil

Plugging Completed 08-21-97

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08-21-97 (date)

by Richard Lacey, District 1 office. (XCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation \_\_\_\_\_ Depth to Top 3556 Bottom 3561 T.O. 3583

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface		244	8 5/8"	244	0
	Production		3582	5 1/2"	3582	1685

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Bottom plug sand and cement to 3506'. Halliburton mixed 300# hulls, 10 sacks gel, 50 sacks cement-10 sacks gel, 100# hulls, released 8 5/8" wooden plug-mixed and pumped 125 sacks cement. Max psi 400#, shut in 200#. Time started 2:50 pm and completed 2:50 pm.

Name of Plugging Contractor D. S. & W. Well Servicing, Inc. License No. 6901

Address P. O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior 8-26-1997

STATE OF Kansas COUNTY OF Barton, ss.

Joseph Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the fact-statement, and matters herein contained and the log of the above-described well, as filed the same are true and correct, so help me God.

(Signature) Joseph Strube


(Address) P. O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 1997

Bonnie L. Connell  
Notary Public

My Commission Expires: April 8, 2001

USE ONLY ONE SIDE OF EACH FORM



Form CP-4  
Revised 05-88