

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

**Well Plugging Record**  
**K.A.R. -82-3-117**

API NUMBER 15-185-230660000  
LEASE NAME Fischer 'A'  
WELL NUMBER No. 1

TYPE OR PRINT

NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

1860 Ft. from North Line of Section  
910 Ft. from West Line of Section

LEASE OPERATOR Globe Operating, Inc. SPOT LOCATION 80' W & 210' S of C Ne Sw Nw  
ADDRESS P.O. Box 12 Section 31 Township 21s Range 11w  
CITY, STATE, ZIP Great Bend, Kansas 67530 County Stafford  
PHONE # 316-792-7607 Date Well Completed Nov. 12, 1997  
Character of Well Dry and Abandoned Date Plugging Commenced Nov. 12, 1997  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed Nov. 12, 1997

The plugging proposal was approved on November F9810, 1997 at 9:00 am (date)  
by Steve Durrant (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 3570

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	112	and		
Redbeds	Shale/Siltstone	112	275	8-5/8"	259.66	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Plugged well with : Heavy mud from 3570' to 570' then 50 sacks of cement,  
then heavy mud to 300' then 50 sacks cement then heavy mud to 40' then 10 sacks.  
Plugged rathole with 15 sacks and mousehole with 10 sacks using 60/40 Poz, 6% Gel.  
Received plugging orders at 9:00 am on 11/10/97 from Steve Durrant. Started  
plugging well at 8:30 pm and plug down at 10:30 pm on 11/12/97 by Allied. Ticket #9665.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Operating, Inc. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of  
the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124


SUBSCRIBED AND SWORN TO me this 13<sup>th</sup> day of January, 19 98

RECEIVED  
STATE CORPORATION COMMISSION

JAN 15 1998 1-15-98

Virginia Lee Smith  
(Notary Public)

My Commission Expires: August 25, 2000



**Sterling Drilling Company, Rig #4**

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (316) 672-9508, Fax 672-9509

**SAMPLE LOG****Fischer 'A' No. 1**

**LOCATION:** 80' W & 210' S of C Ne Sw NW Section 31 T 21s R 11w  
**API:** 15-185-230660000 Stafford County, Kansas

**OWNER:** Globe Operating, Inc.  
**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMMENCED:** 07-Nov-97  
**COMPLETED:** 12-Nov-97

**TOTAL DEPTH:** **DRILLER** 3570 FEET  
**LOGGER** Not logged FEET

**Ground Elevation:** 1778  
**KB Elevation:** 1787

**LOG**

0 - 112 FEET Top Soil and Sand  
112 - 865 FEET Redbeds  
865 - 3570 FEET Shale and Limestone

**CASING RECORDS****Surface/Production Casing Data:**

Spud @ 8.15 am on 11-07-97. Drilled 12 1/4" hole to 275'. Ran 7 joints of 20# 8-5/8" surface casing 259.66' set at 271' KB. Cemented with 230 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 1:30pm on 11/07/97 by Allied. Good returns. Ticket # 4442.

Plugged well with : Heavy mud from 3570' to 570' then 50 sacks of cement, then heavy mud to 300' then 50 sacks cement then heavy mud to 40' then 10 sacks. Plugged rathole with 15 sacks and mousehole with 10 sacks using 60/40 Poz, 6% Gel.

Received plugging orders at 9:00 am on 11/10/97 from Steve Durrant. Started plugging well at 8:30 pm and plug down at 10:30 pm on 11/12/97 by Allied. Ticket #9665.

**DEVIATION SURVEYS**

1/4 degree(s) at 275 feet  
1-3/4 degree(s) at 3440 feet

JAN 15 1990

CONVENTION DIVISION  
Wichita, Kansas