

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,782-0000

LEASE NAME Mallies-Fischer

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 31 TWP. 21 RGE. 11 (E or W)

COUNTY Stafford

Date Well Completed 07-14-91

Plugging Commenced 07-14-91

Plugging Completed 07-15-91

LEASE OPERATOR Dawson-Markwell Exploration Co.

ADDRESS 3620 N.W. 58th Oklahoma City, OK 73112

PHONE# (405) 947-2587 OPERATORS LICENSE NO. 5558

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 07-10-91 (date)

by Dick Kapp (KCC District Agent's Name).

to be filed
Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3698'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

7-17-91
JUL 17 1991

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 3593' w/50 sacks cement thru drill pipe

Next Plug: @ 572' w/50 sacks " " " " 15 sacks in Rat Hole

Next Plug: @ 300' w/50 " " " " "

Top Plug: @ 40' w/10 " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dawson-Markwell Exploration Co.

STATE OF Kansas COUNTY OF Barton, ss.

Larry Curtis (Employee of Operator) or ~~(Owner)~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.


(Signature) Larry Curtis

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 91

Paula Ann Laudick
Notary Public

My Commission Expires: _____



DRILLER'S WELL LOG

DATE COMMENCED: July 9, 1991
DATE COMPLETED: July 15, 1991

Dawson-Markwell Exploration Co.
MALLIES - FISCHER #1
C W/2 SW SW
Sec. 31, T21S, R11W
Stafford County, Ks.

- 0 - 75' Surface Soil, Sand
- 75 - 550' Red Bed
- 500 - 572' Anhydrite
- 572 - 1390' Shale
- 1390 - 2050' Shale w/Lime Streaks
- 2050 - 3058' Lime & Shale
- 3058 - 3090' Shale & Lime
- 3090 - 3186' Shale
- 3186 - 3440' Lime
- 3440 - 3456' Shale & Lime
- 3456 - 3555' Chert
- 3555 - 3576' Sand
- 3576 - 3698' Dolomite
- 3698' RTD

ELEVATION: 1789 K.B.

Surface Pipe: Set used
8-5/8", 28# pipe @258'
w/170 sacks 60/40 pozmix
2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) SS

Larry Curtis of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 16th day of July 1991.



Paula Ann Laudick
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1991
CONSERVATION DIVISION
Wichita, Kansas