


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kans.

Rice County. Sec. 15 Twp. 21 Rge. (E) 7 (W)

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Abe Mizel
Lease Name Hauschild Well No. 1
Office Address 501 Enterprise Building, Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed September 15 ~~XXXXXX~~ 19 40
Application for plugging filed _____ 19 _____
Application for plugging approved February 5 19 59
Plugging commenced February 9 19 59
Plugging completed February 16 19 _____
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	3380	2406

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3375'. Dumped 6 sacks of cement. Shot pipe off at 2406'. Pulled pipe and mudded hole to 210'. Set rock bridge and dumped 30 sacks of cement. Finished mudding hole and dumped 10 sacks of cement at base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1959

CONSERVATION DIVISION
Wichita

3-16-1959

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kans. COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Selby
R. R. #4, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of Feb. 19 59

Horothy Selby Notary Public.

My commission expires August 12, 1961


PLUGGING
FILE SEC 15 T 21 R 7W
BOOK PAGE 14 LINE 13

H. B. GARDEN
 John Hauschild "A" No. 1.

SEC. 15 T. 21 R. 7W
 C&L NE SE

Total Depth. 3392'
 Comm. 8-27-40 Comp. 9-15-40
 Shot or Treater.
 Contractor.
 Issued. 11-9-40

County. Ring



CASING:
 15" 79'
 7" 3380'

Elevation.

Production. Pot. 1232 B.
 2 BW

Figures Indicate Bottom of Formations.

no log	79
red rock & gyp	320
shale & shells	640
salt	920
shale & shells	1265
shale & lime	1335
lime sdv	1565
shale & lime	1730
shale	1855
shale & shells	2040
shale & lime	2300
lime brkn	2350
shale & shells	2393
lime brkn	2410
shale & lime	2440
lime	2450
lime brkn	2528
lime	2715
shale & lime shells	2800
lime	2860
shale	2942
lime Kansas City	3080
lime	3260
shale	3269
lime brkn	3290
shale	3305
lime	3325
lime brkn	3335
shale	3370
conglomerate	3380
Cable Tools	
conglomerate	3392
Total Depth.	

1st oil 3380
 1st flow 3388

RECEIVED
 STATE CORPORATION COMMISSION

MAR 16 1950

CONSE
 W

PLUGGING
 FILE SEC 15 T 21 R 7W
 BOOK PAGE 14 LINE 13