


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County. Sec. 15 Twp. 21 Rge. (E) 7 (W)
Location as "NE/CNW/SW" or footage from lines CWL E 1/2 SE
Lease Owner. Abe Mizel
Lease Name. Hauschild Well No. 2
Office Address. 501 Enterprise Building, Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed June 12 19 39
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced January 29 19 59
Plugging completed February 4 19 59
Reason for abandonment of well or producing formation



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Toman
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	3380	2834

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand to 3375'. Dumped 6 sacks of cement. Shot pipe off at 2834'. Pulled pipe and mudded hole to 210'. Set rock bridge and dumped 30 sacks of cement. Finished mudding hole and dumped 10 sacks of cement at top of surface.

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1959

CONSERVATION DIVISION
WICHITA, KANSAS

3-16-1959

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF Kans. COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. #4, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of February, 19 59

My commission expires August 12, 1961

Dorothy Selz
Notary Public.

PLUGGING
FILE SEC. 15 T. 21 R. 7W
BOOK PAGE 14 LINE 14

H.B. GARDEN
 J. Hauschild No. 2-A.


SEC. 15 T. 21 R. 7W.
 CNL E 1/2 SE

Total Depth. 3391
 Log. 5-3-39 Comp. 6-13-39
 Sp. or T. of Log.
 Driller.
 I. Mud. 10-7-39

County Pice.

CASING.

12" 100' 7" 3391'



Elevation.

Production. Pot. 743 B.

Figures Indicate Section of Formations.

clay	18
sand water	62
red rock	100
shale and shells	300
shale	370
salt	490
shale	1000
broken lime	1205
lime	1510
broken lime sticky shale	1605
lime and shale	1691
lime	1740
shale and lime	1999
shale and shells	2175
lime shells and shale	2390
lime	2695
shale	2705
lime	2740
shale	2800
lime	2861
shale	2893
lime	3139
red rock	3173
lime	3213
lime broken	3211
lime	3340
shale	3378
false conglomerate	3380
conglomerate	3387
oil level 2500	
conglomerate	3391

Total Depth.

RECEIVED
 STATE CORPORATION COMMISSION

MAR 16 1959

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 15 T. 21 R. 7W.
 BOOK PAGE 14 LINE 14