


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County. Sec. 15 Twp. 21 Rge. 1 (E) 7 (W)
Location as "NE/CNW/SW" or footage from lines CEL SE 1/4
Lease Owner Abe Mizel
Lease Name Hauschild Well No. 4A
Office Address 501 Enterprise Building, Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed December 1 1939
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced January 15 1959
Plugging completed January 24 1959
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | 7" | 3383 | 2775 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back with sand to 3375'. Dumped 6 sacks of cement.
Shot pipe off at 2775'. Pulled pipe and mudded hole to
210'. Set rock bridge and dumped 30 sacks of cement.
Finished mudding hole and dumped 10 sacks of cement at
base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kans. COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) [Signature]
R. R. #4, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of January, 19 59

My commission expires August 12, 1961 _____ Notary Public.


PLUGGING
FILE SEC 15 T 21 R 7W
BOOK PAGE 14 LINE 15

H.B.GARDEN
 Hauschild No. 4-A

SEC. 15 T. 21 R. 7W
 CEL SE $\frac{1}{2}$

Total Depth. 3391
 Comm. 11-7-39 Comp. 12- 1-39
 Shot or Treated.
 Contractor.
 Issued. 1-13-40

County Rice.



CASING.

12 $\frac{1}{2}$ " 77'
 7" 3383'

Elevation

Production. Pot. 746 B.

Figures Indicate Bottom of Formations.

| | | | |
|--------------------------|------|------------------|------|
| cellar | 8 | lime | 2993 |
| surface | 16 | sdv lime | 3034 |
| sand | 53 | limo | 3150 |
| red rock and shale | 70 | limo pyrito | 3184 |
| shells | 77 | lime | 3296 |
| red rock and gyp | 339 | limo | 3361 |
| red rock, shale & shells | 628 | shale shells | 3365 |
| salt | 925 | shale | 3378 |
| lime and shale | 1000 | conglomerate | 3391 |
| lime | 1060 | Total Depth | |
| shale and shells | 1066 | Top Conglomerate | 3379 |
| lime shells | 1081 | | |
| lime | 1100 | | |
| lime shells and shale | 1199 | | |
| broken lime | 1340 | | |
| lime | 1417 | | |
| broken lime and shale | 1541 | | |
| shale | 1554 | | |
| shale and lime | 1650 | | |
| lime | 1715 | | |
| lime and shale | 1740 | | |
| lime | 1785 | | |
| shale shells | 2005 | | |
| lime and shale | 2300 | | |
| limo | 2389 | | |
| sdv limo | 2414 | | |
| lime | 2705 | | |
| shale lime shells | 2755 | | |
| sand | 2775 | | |
| lime and shale | 2803 | | |
| lime | 2816 | | |
| limo and shale | 2803 | | |
| limo | 2816 | | |
| lime and shale | 2869 | | |
| shale | 2915 | | |

RECEIVED
 STATE CORPORATION

MAR 1 1940

PLUGGING
 FILE SEC. 15 T. 21 R. 7W
 BOOK PAGE 14 LINE 15