

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

Strike out upper line
when reporting plug-
ging off formations.

Rice County. Sec. 15 Twp. 21 Rge. 7W ~~(E)~~///(W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW NE
Lease Owner Glickman Iron & Supply Co. S & S Supply Co.
Lease Name Hauschild
Office Address 7110 Box 1613, Wichita, Kansas Well No. 3
Character of Well (completed as Oil, Gas or Dry Hole) Abandoned Oil Well
Date well completed September 8, 1936
Application for plugging filed March 24, 1944
Application for plugging approved March 25, 1944
Plugging commenced September 3, 1944
Plugging completed September 5, 1944
Reason for abandonment of well or producing formation Oil depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....Yes
Ruel Durkee

Name of Conservation Agent who supervised plugging of this well.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3398 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

6 sax of cement dumped at 3380 feet
30 sax of cement dumped at 150 feet
10 sax of cement dumped at top of surface
pipe. Filled with mud between cement
plugs.

(If additional description is necessary, use BACK of this sheet.)
Correspondence regarding this well should be addressed to Glickman Iron & Supply Co.; S & S Supply Co.
Address Box 1613, 119 N. Boston, Tulsa, Oklahoma
Wichita, Kansas


STATE OF....., COUNTY OF....., ss.
..... (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. M. Hurstman

SUBSCRIBED AND SWORN to before me this 13th day of March, 1948

(Address) John F. Mount
Notary Public.

My commission expires Dec. 4, 1950
My commission expires.....



3-13-1948

15.159. 35699.0000

Hauschild No. 3

Sec. 15 T. 21 R. 7W
SW NW NE
900' S NL 410' E WL W/2 NE/4

Total Depth. 3399'
Comm. 8-26-36 Comp. 9-8-36
Shot or Treated.
Contractor. E.J. Shaffer

County. Rice

CASING:
12 1/2" 105'
6 5/8" 3380'

Production. Pot. 1463 B.

Figures Indicate Bottom of Formations.

Cellar	13
Sand	73
Shale & Red Bed	92
Red Bed	105
Shale & Salt	1100
Shale & Shells	1270
Shale & Lime	1650
Straight hole test 1500'	
1 degree off	
Shale	1835
Shale	2160
Straight hole test 2000'	
1/2 degree off	
Shale & few Shells	
(Lime)	2237
Shale & Lime Shells	2350
Shale brkn	2457
Lime & Shells	2553
Lime & Shale	2635
Lime	2863
Shale & Lime	2973
Lime	3000
Shale Red	3035
Shale & Lime	3053
Lime	3277
Shale	3325
Lime	3351
Lime & Shale	3366
Coring	3369
Coring Lime & Red Rock	3379
Cored	3388
Reaming	3380
Conglomerate	3399
Total Depth.	

PLUGGING	
FILE	SEC 15 T 21 R 7W
BOOK	PAGE 112 LINE 6

Bridgeport Oil Company, Inc.



Production of Crude Oil

GENERAL OFFICES — WICHITA 1, KANSAS

March 24, 1944

Re: Hauschild #3
SW NW NE 15-21S-7W

Hauschild "A" #5
C S/2 SW NE/4 15-21S-7W

Hauschild "A" #6
C N/2 SW NE/4 15-21S-7W
Wherry Pool
Rice County, Kansas.

Conservation Division,
State Corporation Commission,
800 Bitting Building,
Wichita, Kansas.

Gentlemen:

Attached are Well Plugging Applications Forms
and Logs covering the captioned wells.

Very truly yours,

BRIDGEPORT OIL COMPANY, INC.

Frank Leach
Production Manager

FL/bls
att. (6)

