

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) **RECEIVED**
STATE CORPORATION COMMISSION

MAY 10 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.Operator's full Name: K & E Drilling, Inc.Complete Address: 719 Union Center, Wichita, KansasLease Name: Robinson "A" Well No. #1Location: C SE SW Sec. 31 Twp. 30 Rge. 9 (E) (W) WCounty Kingman Total Depth 4460' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Rider was instructed to plug the well as follows:

228' of 8 5/8" surface pipe, cement circulated with 250 sacks.
Fill hole with drilling mud to 225', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
.2 sacks.

Very truly yours,

Archie Elving