

State of Kansas



JOHN ANDERSON, Jr. Governor  
 WILLIAM L. MITCHELL Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY O. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

APR 9 1965

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Dear Sir:

Mr. Jack Sullivan of Sierra Petroleum Co., Inc. has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Sierra Petroleum Co., Inc.

Complete Address: 1015 Wichita Plaza, Wichita, Kansas

Lease Name: Du Mars Well No. # 1

Location: SE NW SE Sec. 11 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4346' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

242' of 8 5/8" surface pipe, cement circulated with 175 sacks.

Fill hole with drilling mud to 240', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent