

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 5 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Anderson of William H. Pine has this date requested permission to plug the following described well:

Mr. Anderson guarantees payment of the plugging fee.

Operator's full Name: William H. Pine

Complete Address: McCulloch Building Okmulgee, Oklahoma

Lease Name: Young Well No. 1

Location: C SE NW Sec. 19 Twp. 17 Rge. 20 (E)(W) X

County Rush Total Depth 4165' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Anderson was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace 25 sc cement thru drill pipe. Heavy mud to 260' set cementing plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/3 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Leo Massey
Conservation Division Agent