



15.165.20836.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 16 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Cotton of H-30 Drlg. has this

date requested permission to plug the following described well:

Mr. Cotton guarantees payment of the plugging fee.

Operator's full Name: Parrish Oil Co. & H-30, Inc.

Complete Address: 120 N. Market, Suite 201, Wichita, Ks.

Lease Name: Young Well No. 1

Location: 150' E of SW NW Sec. 31 Twp. 19 Rge. (E)(W) 20

County: Rush Total Depth 4410' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cotton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 500' thru drill

pipe. Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

L. J. Massery
Conservation Division Agent