

15.165.20222.00.00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

WICHITA, KANSAS

RECEIVED

MAR 14 1969
CONSERVATION DIVISION
Wichita, Kansas

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Howard of Sage Drlg. has this

date requested permission to plug the following described well:

Mr. Howard guarantees payment of the plugging fee.

Operator's full Name: Pubco Petroleum Corp.,

Complete Address: Box 567 McCook, Nebr.

Lease Name: Hanzly Well No. 31-8

Location: 150' S of C SE NE Sec. 31 Twp. 19 Rge. 20 (E)(W) X

County Rush Total Depth 4490' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Howard was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace

70 sk cmt thru drill pipe. Heavy mud to 360' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with

2 sk cmt.

Very truly yours,

Law F. Messersmith
Conservation Division Agent