

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell Drlg. has this

date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg & Southwest Petro-Chem

Complete Address: 705 4th Nat'l Bk. Bldg., Wichita, Ks.

Lease Name: Dehner "A" Well No. 8

Location: App. C SE SW Sec. 29 Twp. 29 Rge. (E)(W) 20

County: Rush Total Depth 4385 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Messink
Conservation Division Agent