

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 4 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Flake of Woodman-Iannitti has this

date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Woodman - Iannitti

Complete Address: 706 Union Nat'l Bldg., Wichita, Ks.

Lease Name: Pascoe Well No. 1

Location: U NE SW Sec. 23 Twp. 19 Rge. 20 (E)(W) X

County: Rush Total Depth 4375 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Flake was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace  
70 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Red A. Massey  
 Conservation Division Agent