



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
WICHITA, KANSAS

5-12-1975

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of B&B Drlg. has this

date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Martin Oil Co. & Pate-Dombaugh Petro.

Complete Address: 527 Union Center, Wichita, Ks.

Lease Name: Williams Well No. 2

Location: SE SE SW Sec. 12 Twp. 19 Rge. (E)(W) 20

County: Rush Total Depth 4245' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sx cem plug at 500' thru drill
pipe. Heavy mud to 215' set 25 sk cmt plug thru drill pipe. Heavy mud
to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Messing
Conservation Division Agent