


STATE OF KANSAS
STATE CORPORATIONS COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

McPherson County, Sec. 16 Twp. 21 Rge. 3W E/W
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines
NE NE SW

Lease Owner Ray Law
Lease Name Edeger #1 Well No. _____
Office Address McPherson, Kansas 67460
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4/22/76 19____
Plugging completed 4/26/76 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production
19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3440'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	181	none
				5 1/2"	3435'	1707'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded to 3300' and ran 5 sacks cement. Loaded hole, shot pipe at 1693', pulled 58 joints. Plugged well with 4 sacks hulls, 20 sacks gel... and 100 sacks cement, 50-50 pos.

PLUGGING COMPLETE.

APR 30 1976

CONSERVATION DIVISION
Wichita, Kansas

4-30-1976

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS


SUBSCRIBED AND SWORN TO before me this 27th day of April (Address) 76 1976

My commission expires _____



Margaret Melcher
Notary Public.

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, KansasCompany. LINDAS OIL CO.
Farm. Ediger No. 1SEC. 16 T. 21 R. 3W
SE NE NE SW
380' fr NL, 200' fr EL
SW/4Total Depth. 3436
Comm. 6-22-54 Comp. 7-5-54
Shot or Treated.
Contractor. Musgrove Petroleum Corp.
Issued. 9-18-54County McPherson
KANSAS

Elevation. 1458

Production Swb, 17 BO, 5% wtr

CASING:

8 5/8 @ 181' w/ 160 sx cmt.
5 1/2 @ 3535' w/ 100 sx cmt.

Figures indicate Bottom of Formations.

sand	146
shale	390
lime	780
lime & shale	940
lime	1080
lime & shale	2445
lime, shale & sand	2530
lime & shale	2579
lime	2900
lime & shale	3046
lime	3115
lime & shale	3225
lime, cherty lime & shale	3436
Total Depth	

TOPS:

Mississippi	2997
Kinderhook	3058
Maquoketa	3213
Viola	3332
Simpson	3355
Arbuckle	3434

DST #1: 3355-77, open 1 hr. fair
steady blow, rec. 88' water mud,
240' formation water, IFP 30#, FFP
150#, BHP 285#/ 15 min.

JUN 22 1956