


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 West 10th Street
Wichita, Kansas

McPherson County. Sec. 16 Twp. 21S Rge. 3W (#) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner K & E Drilling, Inc.
Lease Name Flaming Well No. 1
Office Address 1006 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 24 19 53
Application for plugging filed February 24 19 53
Application for plugging approved February 24 19 53
Plugging commenced 1:00 a.m., February 24 19 53
Plugging completed 8:00 a.m., February 24 19 53
Reason for abandonment of well or producing formation Commercial quantity
of oil not found



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8 "	231'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 240' w/25 sacks cement. Set top plug at 20' with 5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1953

CONSERVATION DIVISION
Wichita, Kansas

3-17-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E Drilling, Inc.
Address 1006 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Clinton Engstrand, agent for (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clinton Engstrand
1006 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12 day of March, 1953

Waldemar Rogers
Notary Public.

My commission expires October 29, 1955



PLUGGING
FILE SEC 16 T 21 R 37
BOOK PAGE 81 LINE 27

15.113.01579.0000

K & E DRILLING, INC.
NO. 1 FLAMING

NE NE NW Sec. 16-21S-3W
McPherson County, Kansas

Casing
8 5/8" Set @ 231'

Cement
175 Sacks

Comm: 2-11-53
Comp: 2-24-53
Total Depth: 3560'

FORMATION	DEPTH
Clay	0 - 30
Sand	30 - 70
Sand (strks of clay)	70 - 190
Blue shale and clay	190 - 231
Shale and shells (strks of sand)	231 - 435
Anhydrite	435 - 445
Anhydrite	445 - 462
Lime	462 - 590
Shale and lime	590 - 750
Lime	750 - 783
Lime and shale	783 - 906
Shale and lime	906 - 980
Lime and shale	980 - 1590
Shale and lime shells	1590 - 1725
Lime	1725 - 1785
Shale	1785 - 1805
Shale and lime	1805 - 1990
Lime	1990 - 2082
Lime	2082 - 2180
Shale and shells	2180 - 2285
Lime and shale	2285 - 2453
Lime	2453 - 2563
Lime	2563 - 2595
Lime and shale	2595 - 2700
Lime	2700 - 2760
Lime	2760 - 2782
Soft bread	2782 - 2802
Lime and shale	2802 - 2842
Lime and shale	2842 - 2914
Shale	2914 - 3015
Cherty lime	3015 - 3022
Lime and shale	3022 - 3035
Lime	3035 - 3099
Shale and lime	3099 - 3110
Lime	3110 - 3143
Lime and shale	3143 - 3258
Shale, lime shells	3258 - 3326
Shale and lime	3326 - 3375
Shale	3375 - 3438
Lime	3438 - 3456
Sand	3456 - 3490
Lime and shale	3490 - 3492
Sand chert	3492 - 3510
Sand and shale	3510 - 3541
Lime	3541 - 3560

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 16 T 21 R 3W
BOOK PAGE 81 LINE 27

STATE OF KANSAS)
SEDGWICK COUNTY) SS

I hereby certify that the above information is true and correct to the best of my knowledge.

Spencer Fitzgerald

Subscribed and sworn to before me this 12 day of March, 1953.

Waldemar Jones
Notary Public

My Commission Expires: 10-29-55