

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-113.30115.0000

LEASE NAME Neufeldt #1

WELL NUMBER _____

SPOT LOCATION E/2 W/2 SE SE

SEC. 16 TWP. 21 RGE. 3w (E) or (W)

COUNTY McPherson

Date Well Completed _____

Plugging Commenced 9/24/85

Plugging Completed 10/4/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Midwestern Supply Co., Inc.

ADDRESS 300 Patton Rd. Great Bend, Ks. 67530

PHONE # (316) 793-8521 OPERATORS LICENSE NO. 8778

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8 | 245' | none |
| | | | | 4 1/2" | 3467' | 2204' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3430' & 4 sacks cement. Shot pipe at 2900', 2700', 2500', 2300', & 2204'. Pulled 67 joints of pipe. Plugged well with 5 hulls, 10 gel, 8 5/8 plug, & 125 sacks 60/40 poz 4% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED
STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

OCT 10 1985

CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 85

Irene Hoover
Notary Public

My Commission expires:



WELL LOG - NEUFELDT NO. 1 - PRODUCER

Donald T. Ingling et al, Lease Owner

Section 16-21-3W

Donald T. Ingling, Contractor

Location: E/2 W/2 SE SE

Commenced: 3-11-66

County: Sedgewick

Completed: 3-22-66

Production:

Total Depth: 3480' (rotary)

Elevation: 1456' RE

Casing: 8 5/8" 245' (115 sacks cement)
4 1/2" 3467' (140 sacks cement)

Figures below indicate bottom formation

| | |
|------|------------------------|
| 40 | surface clay |
| 125 | sand and shale streaks |
| 220 | shale |
| 245 | shale and shells |
| 335 | shale and lime streaks |
| 710 | shale and lime |
| 872 | shale and lime streaks |
| 940 | shale and lime streaks |
| 1110 | lime and shale |
| 1490 | shale and shells |
| 1775 | shale |
| 1920 | shale and lime |
| 1975 | shale and lime |
| 2095 | lime |
| 2350 | shale and lime |
| 2440 | shale |
| 2595 | lime |
| 2696 | lime |
| 2780 | lime |
| 2850 | shale and lime |
| 2930 | lime and shale |
| 3030 | shale |
| 3110 | lime |
| 3163 | lime |
| 3220 | lime |
| 3285 | shale |
| 3314 | shale |
| 3400 | shale and sand |
| 3469 | shale and sand |
| 3480 | sand - Simpson |
| 3480 | Total Depth |

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1966

CONSERVATION DIVISION
Wichita, Kansas

I certify this is a true and correct copy of the above mentioned well.

STATE OF KANSAS)
) ss.
SEDEGWICK COUNTY)

Donald T. Ingling

Subscribed and sworn to before me, a Notary Public, in said county and state.

M E Black
Notary Public

My commission expires: Feb. 27, 1968