

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.113.20785.0000

LEASE NAME Neufeldt #2

WELL NUMBER _____

SPOT LOCATION C S/2 SE

SEC. 16 TWP. 21 RGE. 3w (E) or (W)

COUNTY McPherson

Date Well Completed _____

Plugging Commenced 9/18/85

Plugging Completed 10/4/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Midwestern Supply Co., Inc.

ADDRESS 300 Patton Rd., Great Bend, Ks. 67530

PHONE # (316) 793-8521 OPERATORS LICENSE NO. 8778

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3345'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	243'	none
				4 1/2"	3344'	2167'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3015' & 4 sacks cement. Shot pipe at 2700', 2500', 2300', & 2167'. Pulled 54 joints of pipe. Plugged well with 10 gel, 5 hulls, and 125 sacks 60/40 poz 4% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss. STATE CORPORATION COMMISSION

R. Darrell Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

OCT 10 1985

CONSERVATION DIVISION
Wichita, Kansas


(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 7th day of October, 1985

Irene Hoover
Notary Public

My Commission expires:



K.G.S. LIBRARY

Netro-Log

Gamma Ray Neutron

COMPANY <u>DONALD T. INGLING</u>	
WELL <u>NEUFELDT #2</u>	RELEASED NO SMALL SCALE
FIELD _____	
COUNTY <u>MC PHERSON</u>	STATE <u>KANSAS</u>
Location <u>C/S/2-SE/4</u>	Other Services:
Sec. <u>16</u> Twp. <u>21S</u> Rge. <u>3W</u>	
Permanent Datum: <u>GROUND LEVEL</u> Elev. <u>1453</u>	Elev.: K.B. <u>1458</u>
Log Measured From <u>K.B.</u> , <u>5</u> Ft. Above Perm. Datum	D.F. <u>1456</u>
Drilling Measured From <u>KELLY BUSHING</u>	G.L. <u>1453</u>

Date	1/16/81		
Run No.	ONE		
Depth-Driller	3345	K.G.S. LIBRARY	
Depth-Logger	3328	K.G.S. LIBRARY	
Bit Log Inter.	3327	K.G.S. LIBRARY	
Top Log Inter.	2500	STATE OF KANSAS	
Casing-Driller	8 5/8 @ 245	@	@
Casing-Logger			
Bit Size	7 7/8	AUG 22 1985	
Type Fluid in Hole	WATER		
Dens.	Visc.		
pH	Fluid Loss	ml	ml
Source of Sample			
R ₁₀ @ Meas. Temp.	@	'F	@
R ₁₅ @ Meas. Temp.	@	'F	@
R ₂₀ @ Meas. Temp.	@	'F	@
Source: R ₁₀ R ₁₅			
R ₁₀ @ BHT	@	'F	@
Time Since Circ.			
Max. Rec. Temp.	'F	'F	'F
Equip. Location	H-6 CB		
Recorded By	RON LEWIS		
Witnessed By	MR. BILL WITCRAFT		