

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION FORM CP-4
REV. 1-15-80

APR 21 1982

CONSERVATION DIVISION
Wichita Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY McPherson SEC. 25 TWP. 21S RGE. 2W E/W
Location as in quarters or footage from lines:
W/2 SW NE

Lease Owner F & M Oil Company
Lease Name Rupp #1 Well No. _____
Office Address 422 Union Center Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced _____ 2-17-82
Plugging completed _____ 4-15-82
Reason for abandonment of well or producing formation _____
Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merlan Unruh
Producing formation _____ Depth to top _____ bottom _____ T.D. 3418'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	248'	none
				5-1/2"	3100'	2586'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

~~Plugged off bottom with sand to 2950' and ran 4 sacks cement. Shot casing @2585', pulled 64
joints of 5-1/2" casing. Plugged well with 3 sacks hulls, 5 sacks gel, 8 5/8" plug
125 sacks 50/50 pos, 2% cc.~~

~~Plugging Complete.~~

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF KANSAS COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 19 82



Irene Hoover
Notary Public.

My Commission expires:

KANSAS

IMPORTANT
Kans. Geo. Survey request
samples on this well.


WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 25 T. 21 R. 2 ^E/_W

Loc. W2 SW NE

County McPherson

640 Acres
N



Elev.: Gr. 1485

DF _____ KB _____

API No. 15 — 113 — 20,823 . 0000
County Number

Operator
F & M Oil Co., Inc.

Address
422 Union Center Wichita, Kansas 67202

Well No. #1 Lease Name
Rupp

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Big Springs Drilling, Inc. Geologist
Roger Fisher

Spud Date 2-20-81 Date Completed 2-27-81 Total Depth 3418 P.B.T.D.
3007

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/2"	8-5/8"		248'	common	175	2% gel, 3% CC
Production		4 1/2"		3100'	60-40 Per	100	2% gel 10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
			4	DP 1/2"	2996-3004

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 gal 15% Nov F	2996-3004

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil _____ Gas _____ Water _____ Gas-oil ratio _____
Disposition of gas (vented, used on lease or sold)	Producing interval(s)

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1981
CONSERVATION DIVISION
Wichita, Kansas

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator F & M OIL CO., INC.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Rupp	Gas
S 25 T 21S R 2W X W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 2992-3025, 30-45-60-60. Strong blow throughout test. Gauged on 1st opening - 5" 298,000, 15" 192,000, 25" 162,000, 2nd opening - 10 " 148,000, 20" 114,000, 30" 96,500, 40" 85,400, 50" 74,000. Recovered 60' thin gas cut mud. FP's 137-63, SIP's 683-610.			<u>SAMPLE TOPS:</u>	
			Cherokee	2928 (-1438)
			Mississippi	2988 (-1498)
			Lansing	2342 (- 852)
			B/KC	2723 (-1233)
			Marmaton	2744 (-1254)
			Osage	3049 (-1559)
			Burlington	3088 (-1598)
			Hunton	3378 (-1888)
			Misner Sand	3375 (-1885)
			<u>ELECTRIC LOG TOPS:</u>	
			Lansing	2343 (- 853)
			B/KC	2718 (-1228)
			Marmaton	2744 (-1254)
			Cherokee	2928 (-1438)
			Mississippi	2989 (-1499)
			Osage	3050 (-1560)
			Burlington	3094 (-1604)
			Kinderhook	3327 (-1837)
			Misner Sand	3378 (-1891)
		RTD	3415	
		LTD	3418	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	_____ Signature
	_____ President Title
	_____ Date