

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-113-21,192-0000

LEASE NAME Rupp

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4950 Ft. from S Section Line

775 Ft. from E Section Line

LEASE OPERATOR Pintail Petroleum

SEC. 25 TWP. 21 RGE. 2 (E) or (W)

ADDRESS 412 E. Douglas Suite #1 Wichita, Ks.

COUNTY McPherson

PHONE#(316) 263-2243 OPERATORS LICENSE NO. 5086

Date Well Completed 8-10-87

Character of Well dry

Plugging Commenced 8-10-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-10-87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita - Tuttle

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	211	8 5/8'	Cemented	to surface

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Filled hole from 3530' to 250' with 50 vis. mud. Mixed 50 sx. Spot plugged at 250'. Fill to 40'. Mix 10 sx. Spot plug from 40' to ground level. Fill rathole with 10 sacks

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Berentz Drilling Co., Inc. License No. 5892

Address P. O. Box 428 Eureka, Kansas 67045

STATE OF Kansas COUNTY OF Greenwood, ss.

Kevin F. Hough (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the same of the above-described well as filed that the same are true and correct, so help me God.

AUG 17 1987 (Signature) [Signature]

(Address) P. O. Box 428 Eureka, KS.

CONSERVATION DIVISION

SUBSCRIBED AND SWORN TO before me this 13th day of August, 19 87

Mary Alice Evenson  
Notary Public



My Commission Expires: 9-1-89

## L O G O F W E L L

Rupp #1  
 NW NE NE  
 Section 25-21-2W  
 McPherson County, Ks.

OPERATOR: Pintail Petroleum

CONTRACTOR: Berentz Drilling Co., Inc.

Commenced with Rotary 8-3-87  
 Completed with Rotary 8-10-87

Casing: 8 5/8"-----211' cemented with 150 sacks

Soil	3'
Sand & Shale	215'
Lime	565'
Shale & Lime	770'
Shale	985'
Lime	1045'
Shale	1672'
Shale & Lime	1975'
Lime	2063'
Sand	2074'
Lime & Shale	2020'
Shale	2156'
Sand Douglas	2221'
Shale	2344'
Lime Lansing K.C.	2721'
Shale	2985'
Lime Mississippi	3318'
Shale Kinderhook	3375'
Lime Hunton	3482'
Viola	3512'
Simpson	3530' R.T.D.

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 17 1987

CONSERVATION DIVISION  
 Wichita, Kansas