


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 19 Twp 21S Rge. 23 (W)  
Location as "NE/CNWSW" or footage from lines 150' N SE SW  
Lease Owner Pickrell Drilling Company  
Lease Name Whipple "B" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 2 1973  
Application for plugging filed April 2 1973  
Application for plugging approved April 2 1973  
Plugging commenced April 2 1973  
Plugging completed April 2 1973  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4617 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	239	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug @ 800' w/80 sacks, Middle Plug @ 240'  
w/30 sacks, Top Plug @ 45' w/15 sacks

RECEIVED  
STATE CORPORATION COMMISSION

APR 6 1973

CONSERVATION DIVISION  
Wichita, Kansas

4-6-73

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of April, 1973

My commission expires August 19, 1975

Helen L. Martin  
Notary Public.



1954  
1955

1956

1957  
1958

**ROTARY DRILLING LOG**

15.083.20291.0000

**COMPANY:** Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202

Rotary Drilling Commenced 3/15/73

Rotary Drilling Completed 4/2/73

**LOCATION:** Whipple "B" No. 1, 150' N SE SW Sec. 19-21S-23W  
Hodgeman County, Kansas

**CONTRACTOR:** **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

**CASING RECORD:**

Run 6 Jts. 8-5/8" surface casing set @ 239' KB. Cemented with 150 sacks. Completed 9:30 P.M. Circulated.

No oil string run, D & A, Plugged down 11:00 A.M. April 2, 1973.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

150	Clay, Rock Post, Clay, Sand-Clay	<u>C.F.S.</u>
240	Shale	4385
385	Shale & Sand Streaks	4395
800	Shale - Sand	4525
1013	Red Beds	4585
1050	Blain	4605
1102	Red Beds - Shale	4610
1320	Sand	4617
1450	Shale - Red Beds	
1633	Red Bed - Shale	
1672	Anhydrite	
1870	Shale - Red Bed - Brown Lime	
2280	Shale & Lime	
2390	Lime	
2565	Shale - Lime	
3240	Lime	<u>Slope Tests</u>
3420	Lime - Shale	2000
3729	Shale & Lime	2500
3885	Sandy Shale	3000
3980	Shale - Lime	3500
4500	Lime	4000
4550	Lime - Chert - Shale	4500
4605	Lime - Chert	4600
4617	Mississippi, RTD	

**RECEIVED**  
STATE CORPORATION COMMISSION  
APR 6 1973  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By *C. W. Sebitts*  
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 4 day of April, 19 73, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 19, 1975

*Helen L. Martin*  
Helen L. Martin Notary Public