

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-02389-00-00
Spot: NENE Sec/Twnshp/Rge: 23-26S-14E
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: LAUBER Well #: 11
County: WOODSON Total Vertical Depth: 1295 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1222		110 SX
SURF	12	512		9999 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2018 2:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 1278', "GEL THE WELL UP" (PMP IN A MIXTURE OF BENTONITE & WTR), FOLLOWED BY A 200' CMT PLUG ON BTM, PU TBG TO 1020', PMP IN A 50' CMT PLUG, PU TBG TO 700', PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP IN & CIRC CMT TO SURF, POOH TBG, "TOP OFF" PROD CSG W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW PLOW DEPTH, AND CLEAN UP LOC.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2018 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1278', pumped 200' cement plug, pulled tubing to 1020', pumped 50' cement plug, pulled tubing to 700', pumped 50' cement plug, pulled tubing to 250', pumped cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1222	1280		

RECEIVED
KCC DIST # 3
JAN 22 2018
CHANUTE, KS
MH

Remarks:
Plugged through: TBG

INVOICED
JAN 30 2018

District: 03

Signed Mik Dolese
(TECHNICIAN)