

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21641-01-00
Spot: NWNWNE Sec/Twnshp/Rge: 9-31S-20W
5155 feet from S Section Line, 1052 feet from E Section Line
Lease Name: HUCK 3120 Well #: 1-9H
County: COMANCHE Total Vertical Depth: 5202 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5111		WITH 50 SX CMT
COND	20	110		WITH 10 SX CMT
L1	4.5	9584		TOP OF LINER 5161'
PROD	7	5851	1623	WITH 300 SX CMT
SURF	9.625	963		WITH 540 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/18/2018 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5111' WITH 50 SX CMT. PLUG AT 990' WITH 100 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 01/18/2018 12:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5111'. CIRCULATED HOLE WITH 190 BBL MUD THEN SPOTTED 50 SX CMT ON TOP OF CIBP. 1ST PLUG AT 1063' WITH 100 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
8298	8622		
7887	8209		
7500	7794		
7082	7405		
6666	7012		
6278	6612		
5875	6198		
5400	5777		

INVOICED
JAN 20 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES TMD=9584'.

Plugged through: TBG

District: 01

RECEIVED
JAN 22 2018
KCC DODGE CITY

Signed


SA

(TECHNICIAN)