

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-00206-00-01  
Spot: SENWSE Sec/Twnshp/Rge: 11-34S-4W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: CHARLIE Well #: 1-11  
County: SUMNER Total Vertical Depth: 4790 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4688		
PROD	5.5	4783	1504	175 SX
SURF	8.625	274		255 SX
T1	2.875	4271		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2017 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: BRENT MORRIS Company: ORR ENTERPRISES Phone: (405) 429-6002

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/06/2017 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

SET 5 1/2" CIBP @ 4121' PER STEVE VANGIESON W/KCC. CIRCULATE HOLE WITH 90 BLS MUD & CAP PLUG WITH 70 SKS CLASS C CEMENT UP TO 3433'. CUT & PULL 5 1/2" CASING FROM 1504 (36 JOINTS). TIH W/TUBING & SPOT 50 SKS CEMENT @ 950'-755'. SPOT 50 SKS CEMENT @ 600'-405. CEMENT DID CIRCUALTE TO SURFACE FROM 300' WITH 100 SKS CEMENT. POH WITH TUBING.

Top	Bot	Thru	Comments
4694	4688		
4302	4280		
4280	4302		


Remarks:

Plugged through: TBG

INVOICED  
JAN 30 2018

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

1/24