

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
265 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-22039-01-00
Spot: SENNENWNW Sec/Twnshp/Rge: 5-34S-6W
350 feet from N Section Line, 1245 feet from W Section Line
Lease Name: MARTIN 3406 Well #: 1-5H
County: HARPER Total Vertical Depth: 5272 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		15 SX
I1	7	5272	1720	330 SX
L1	4.5	8837		
SURF	9.625	697		340 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2017 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: KOLE ATKINSON Company: ORR ENTERPRISES, INC. Phone: (405) 429-6165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 08/31/2017 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TIH WITH CIBP ON TUBING TO 4600' WHERE BP WAS SET. RELEASED BP FROM TUBING & CIRCULATED 176 BBLs OF MUD INSIDE CASING, THEN SPOTTED 70 SX CEMENT. TOH WITH TUBING LAYING DOWN. CUT & PULLED 7" CASING FROM 1720'. TOH WITH CASING. RUN TUBING TO 1150', SPOTTED 50 SX CEMENT. PULLED TUBING TO 750' SPOTTED 50 SX CEMENT. PULLED TUBING TO 300' & CIRCULATED CEMENT TO SURFACE WITH 100 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
8504	8772		
8108	8440		
7747	8031		
7290	7676		
6670	7202		
6482	6786		
6132	6416		
5734	6048		
5308	5658		
4778	5102		


Remarks: ORR ENTERPRISES. CLASS C CEMENT TMD = 8837

Plugged through: TBG

INVOICED
JAN 30 2018

District: 02

Signed _____



(TECHNICIAN)

✓ 2/4