

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-017-20150-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 6-19S-6E
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: HARDER Well #: 11
County: CHASE Total Vertical Depth: 500 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	500		0 SX
SURF	4.5	120		20 SX
SURF	5.5	200		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/24/2017 12:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Revd. from: BOB ROBINSON Company: SHAWMAR OIL & GAS Phone: (620) 382-7565

Proposed Plugging Method: Run 1" to bottom. Circulate cement to surface. Pull 1" to 250' and circulate to surface.

Plugging Proposal Received By: JONATHAN HILL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2017 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

Perfs:

- 1) Rigged up over hole and ran in 1" tubing. Tagged at 200', circulated hole and worked pipe -- unable to work past 200' (well is believed to never have been drilled out of surface casing).
- 2) Mix up 15 sks class A cement (5 sks per bbl) and pump through 1" tubing. Hole circulated fluid but no cement.
- 3) Pulled tubing up to 100', mix up 10 sks class A cement, pump through 1" tubing and circulated cement to surface.
- 4) Pulled tubing out of hole and topped off w/ cement.

INVOICED
JAN 30 2018

Remarks: CEMENTING COMPLETED BY SHAWMAR OIL & GAS. PLUGGED PER COMPLIANCE AGREEMENT (16-CONS-4046-CMSC)

Plugged through: TBG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

