

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-171-21210-00-00  
Spot: SWNENENE Sec/Twnshp/Rge: 35-16S-34W  
600 feet from N Section Line, 335 feet from E Section Line  
Lease Name: JANZEN Well #: 2-35  
County: SCOTT Total Vertical Depth: 4870 feet

Operator License No.: 7311  
Op Name: SHAKESPEARE OIL CO., INC.  
Address: 202 W MAIN ST  
SALEM, IL 62881

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.65	264		WITH 185 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2017 3:30 PM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: DEON VASQUEZ Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 2450' WITH 50 SX CMT. 2ND PLUG AT 1600' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE  
Date/Time Plugging Completed: 12/11/2017 5:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2450' WITH 50 SX CMT. 2ND PLUG AT 1600' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY OES.

Plugged through: DP

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
DEC 12 2017  
KCC DODGE CITY

INVOICED  
JAN 30 2018