

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-19221-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 34-29S-10E
4028 feet from S Section Line, 3301 feet from E Section Line
Lease Name: DUNKLEBERGER Well #: 2
County: ELK Total Vertical Depth: 1280 feet

Operator License No.: 5177
Op Name: SUERTE OIL COMPANY
Address: P.O. BOX 725 128 N. PINE
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1280		0 SX
SURF	8	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: MAURICE PERKINS Company: _____ Phone: (620) 374-2001

Proposed Plugging Method: We have no records at all for this well. Run in with 1" to TD, gel hole, spot 50ft cement plug on bottom, pull 1" out of hole, perforate at 1000ft and 500ft, run 1" tubing in and spot 50ft cement plug at 1000ft, pull to 500ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 12/07/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" tubing to 1400' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 900' and 550'. Ran 1" back into 900' and spotted 10 sack plug. Pulled up to 500' and circulated cement to surface with 155 sacks of cement. A total of 170 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

RECEIVED
KCC DIST # 3
JAN 02 2018
CHANUTE, KS

DS
INVOICED
JAN 30 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed 
(TECHNICIAN)