

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-19230-00-00
Spot: NWSESW Sec/Twnshp/Rge: 34-29S-10E
1018 feet from S Section Line, 3628 feet from E Section Line
Lease Name: ELDEN BURKE Well #: 4
County: ELK Total Vertical Depth: 1390 feet

Operator License No.: 5177 String Size Depth (ft) Pulled (ft) Comments
Op Name: SUERTE OIL COMPANY PROD 6.625 1358 0 SX
Address: P.O. BOX 725 128 N. PINE SURF 8.25 809 0 SX
HOWARD, KS 67349

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/12/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: MAURICE PERKINS Company: Phone: (620) 374-2000

Proposed Plugging Method: Run in with 1" tubing to TD, gel hole, spot 50ft cement plug, pull 1" tubing, perforate at 1000ft and 500ft, run in with 1" tubing and spot 50ft cement plug at 1000ft, pull to 500ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 09/13/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1300' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 900' and 550'. Ran 1" back into 900' and spotted 20 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 150 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1358	1390		

RECEIVED
KCC DIST # 3
DEC 20 2017
CHANUTE, KS

DS


INVOICED
JAN 30 2018

Remarks: WELL WAS PLUGGED BECAUSE IT COULD NOT BE TA'D

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)