

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-20704-00-00  
Spot: SENWNW Sec/Twshp/Rge: 34-29S-10E  
4453 feet from S Section Line, 4420 feet from E Section Line  
Lease Name: DUNKLEBERGER Well #: 29  
County: ELK Total Vertical Depth: 1964 feet

Operator License No.: 5177  
Op Name: SUERTE OIL COMPANY  
Address: P.O. BOX 725 128 N. PINE  
HOWARD. KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1963		0 SX
SURF	8	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/10/2017 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Revd. from: MAURICE PERKINS Company: \_\_\_\_\_ Phone: ( ) 620-2000

Proposed Plugging Method: Run in with 1" tubing to TDF (approx. 1963), gel hole, spot 50ft cement plug, pull 1" tubing out of hole, perforate at 1000ft and 500ft, run in with 1" tubing and spot 50ft plug at 1000ft, pull to 500ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/11/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1900' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 1100' and 550'. Ran 1" back into 1100' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 115 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

RECEIVED  
KCC DIST # 3  
DEC 20 2017  
CHANUTE, KS

DS

INVOICED


JAN 30 2018

Remarks: WELL WAS PLUGGED BECAUSE IT COULD NOT BE TA'D.

Plugged through: TBG

District: 03

Signed \_\_\_\_\_



(TECHNICIAN)