

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25917-00-00
Spot: E2SEWNNE Sec/Twnshp/Rge: 33-20S-22W
990 feet from N Section Line, 1535 feet from E Section Line
Lease Name: BARRICKLOW Well #: 2-33
County: NESS Total Vertical Depth: 4362 feet

Operator License No.: 34876
Op Name: TRIPLE CROWN OPERATING LLC
Address: 2201 S. UTICA PL STE 100
TULSA, OK 74114

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4212		WITH 2 SX CMT
CIBP		4320		
PROD	5.5	4348	1846	WITH 150 SX CMT
SURF	8.625	1430		WITH 650 SX CMT

Well Type: OL UIC Docket No: _____ Date/Time to Plug: 12/12/2017 10:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Revd. from: PRESTON DREILLING Company: DREILLING EXPLORATION Phone: (785) 621-2021

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS WITH 2 SX CMT. PLUG AT 1450' WITH 50 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 12/12/2017 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4212' WITH 2 SX CMT. 1ST PLUG AT 1450' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 350' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4262	4266		

INVOICE
12/12/17

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed

Michael Maier
SA

(TECHNICIAN)

RECEIVED
DEC 27 2017
KCC DODGE CITY