

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-26163-00-00  
Spot: SENESESW Sec/Twnshp/Rge: 4-15S-19W  
780 feet from S Section Line, 2550 feet from W Section Line  
Lease Name: YARNELL-GROSS UNIT Well #: 1  
County: ELLIS Total Vertical Depth: 3763 feet

Operator License No.: 4787  
Op Name: TDL, INC.  
Address: 1310 BISON RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3762		150 SX
SURF	8.625	422		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/13/2017 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: BRETT HOLDERBRAND Company: TDL, INC. DBA Phone: (785) 871-7311

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 400 # hulls and 11 sx gel.  
DV Tool set at 1303' w/155 sx cement.  
Perforations: 3502' - 3504', 3516' - 3519', 3676' - 3678' and 3686' - 3688'  
PBTD: 3718'.  
Anh: 1304'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/13/2017 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran in hole with tubing to 3450'. Quality rigged to tubing and pumped 11 sx gel followed by 50 sx cement w/200 # hulls mixed in. Pulled tubing to 1855' and pumped 180 sx cement w/200 # hulls mixed in to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" casing with a swage and pumped 20 sx cement at 400 psi. Shut in pressure 400 psi. Rigged to 8 5/8" surface casing with instant pressure

GPS: 38.77139 -099.43976

Perfs:

Top	Bot	Thru	Comments
3686	3688		
3676	3678		
3516	3519		
3502	3504		

Remarks: QUALITY OILWELL CEMENTING TICKET # 571

Plugged through: TBG

District: 04

KCC WICHITA

JAN 02 2018

RECEIVED

(TECHNICIAN)

CM

DEC 10 2017

DEC 10 2017

Form CP-2/3

INVOICE  
JAN 20 2018